

KADUR DIVISION.
The 8th January 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kadur division, up to 8th February 1898 for constructing a 1st Class Travellers' Bangalo at Mudgere. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chikmagalur between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a 1st Class Travellers' Bangalo at Mudgere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

DETAILED ABSTRACT ESTIMATE.

Items of work.	Per.	Quantity.
Earthwork excavation and filling basement	C. yds.	154
Burnt stone in chunam (foundation and basement) including bond slabs ..	C. ft.	4,837
Burnt stone in mud	"	1,712
Burnt brick in mortar superstructure	"	7,914
Burnt brick in mud	"	4,095
Arch. work burnt brick in mortar	"	275
Coping with as per plan	R. ft.	60
Burnt stone slabs	S. ft.	1,083
Teak wood work wrought and put up	C. ft.	392
Jungle wood work (reserved)	"	130
Roofing with 1st class Mangalore tiles and teak reapers, &c., complete ..	Sqrs.	72.03
Ridge tiles set in mortar including pointing	R. ft.	191
Flooring with concrete 6" thick and plaster over it	Sqr.	2,857
Do gravel and cowdung washing	"	691
Ventilating tiles	No.	5
Cornice in chunam as per plan	R. ft.	100
Plastering with chunam	Sqrs.	140.48
Do in mud and cowdung washing	"	48.67
Pointing with chunam	"	6.83
White-washing 2 coats	"	139.04
Color washing 2 coats	"	59.11
Teak wood doors panelled with four shutters as per detail (4½' x 7½') including frames, hinges and runlock, &c., complete	S. ft.	67
Teak wood doors panelled with double shutters (4½' x 7½')	S. ft.	540
Do (4' x 7')	"	112
Do (3½' x 6½')	"	91
Teak wood windows with inside glazed shutters 4 x 5½	"	308
Do 3 x 4½	"	54
Do ventilators wing glazed 4' x 2' including frames	Each.	14
Do circular 3½ diameter	"	4
Jungle wood doors battened including frames (3½' x 6') lock, &c.	"	3
Do windows, wooden bars and shutters (2 x 2½) frames	"	2
Do door small (3' x 6') including frames, &c.	"	5
Wood oiling	Sqrs.	50.00
Chocolate painting 2 coats	"	22.90
Teak wood eave boards ordinary	R. ft.	560
Tarring jungle wood work	L. S.	..
Bamboo matting (outer rind)	Sqrs.	26.15
Zinc sheets for valley	S. ft.	216
Constructing cisterns in the bath-rooms with burnt brick in chunam and concrete plaster	No.	4
Clearing site, levelling compound and putting hedges, opening approach roads and sundry works, &c., complete.. ..	..	..

B. SUBBA RAO, Offg. Executive Engr.